

Corrigendum – 3 Dated 08/10/2018

Tender Ref. No: IIT/SRIC/CoE_AMT/DHI/2018/EQ25, dated 20/09/2018

For the tender of Interior & Exterior Decoration

The below mentioned points are to be included in the Annexure – 1 (Scope of Work) in the above mentioned tender document.

Painting
Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade: (a) New work (two or more coats) over and including water thinnable priming coat with cement primer.
Partition Wall
Partition wall or wall panelling with acoustic board or sound absorbing board, 10 mm thick, fixing with aluminium framing, chicken mesh, glass wool with all complete as per instruction.
Wooden Flooring
25mm wooden planking, tongued and grooved in flooring, including fixing with iron screws complete with Second class deodar wood.
False Ceiling
Providing and fixing ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side including) as per IS : 277 and consisting of angle cleats of size 25mm wide X 1.6mm thick with flanges of 27mm and 37mm, at 1200mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9mm running at the spacing of 1200mm centre to centre, to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26mm each having lips of 10.5mm, at 450mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64mm dia x 230 mm long G.I wire at every junction, including fixing perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450mm centre, with 25mm long dry wall screws @ 230mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws @ 230mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with flame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with fully perforated Gypsum Plaster Board of size 1200x 2400x12.5mm having approx. 15% perforated area with perforation size and pattern as approved by the Engineer-in-charge and as per manufacturer's specification, with all 4 side tapered and backed by acoustical tissue with NRC value not less than 0.60.